

VRF Installation



Critical Server Room Back-up Cooling

The installation was commissioned to provide 100% back-up cooling to 3 critical server rooms in the event of primary plant failure and / or cooling during high summer ambients when the primary plant struggled for capacity.

The system was linked into the building management system to provide auto start up if the main chilled water temperature rose above 12deg C or the ambient temperature rose above 25deg C.

The condensing unit base and handrail were constructed and installed under the contract using preferred sub contractors



Site Address

Nationwide
Building
Society
Swindon



Registered
Business



ACCREDITED COMPANY



ACCREDITED COMPANY